UHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
SCHEDULE-B

OF THE WORK: Construction and reparis to culverts in Dasarahalli in ward no. 15 Dasarahalli sub division

	Description of work	Unit	Qty	Rate Quoted by Sri. M Lakkappa	
				In Figures (Rs.)	In Words (Rs.)
	2	3	4	5	6
	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	276	74.0	Rupees Seventy Four Only
2	Plain cement concrete M-10 with OPC cement at 220kg with crushed 40mm down size graded granite metal course aggregate @0.84 CUM and fine agreegate @ 0.6 CM in Foundation mechanically mixed placced in foundation and compacted by vibration including curing for 14 days complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	41.4	5073.0	Rupees Five Thousand Seventy Three Only
3	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specifications.complete as per the direction of Engineer-in-charge of the work	Sqm	481.2	346.0	Rupees Three Hundred Forty Six Only
4	Design Mix M20 with OPC cement @ 320kgs with 20mm & down size graded granite metal course agreegate @ 0.69 CM an Fine agregated 0.46 cm with super plaster @ 3ltrs confirming to IS 9103-1999 Reaffirmed -2008 i.) Upto 5m height complete as per the direction of Engineer-in-charge of the work	Cum	166.98	5917.0	Rupees Five Thousand Nine Hundred Seventeen Only
5	TMT/MS bar Reinforcement KSRRB M2200-6 Supplying, fitting and placing TMT bar reinforcement in Sub-structure complete as per drawing and technical specifications complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Tonne	14.36	49962.0	Rupees Forty Nine Thousand Nine Hundred Sixty Two Only
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per the direction of Engineer-in-charge of the work	Cum	276	68.0	Rupees Sixty Eight Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner